

Our **Kill. Prevent. Protect.**™ process is carried out using our products noted opposite, which are highlighted in the diagram below at each stage that they are applied.



1 Visit property to scope works.



2 Set up AirSanifier temporarily.



3 Check Ventilation.



4 Conclude report.



5 Remove AirSanifier prior to treatment.



6 **A.** Spray any visible mould with FloodHit and wipe down.
B. Apply BioTouch.



7 Carry out strip out works.
If only remedial works required bypass 8-10.



8 Spray any visible mould with FloodHit.



9 Apply Bio-Touch.



10 Commence drying.



11 Set up an AirSanifier and switch on or install one permanently.



**KILL.
PREVENT.
PROTECT.™**



KILL. PREVENT. PROTECT.™



We recognise that mould issues are multifaceted and require more than just a one-size-fits-all approach. Our approach is grounded in the understanding that mould cannot be simply eradicated with a single product. Rather, it demands a comprehensive strategy that considers factors such as condensation, ventilation, sensitivity to harsh chemicals and tenant communication / awareness.

Our solution, 'Kill. Prevent. Protect.™', is designed to mitigate risks associated with mould growth to a safe level, ensuring the well-being of both tenants and your maintenance teams. This approach has been rigorously tested and proven effective, even in high-risk environments such as hospitals during the COVID-19 pandemic.

1 Visit property to scope works.

We will attend every site to scope the works required base upon our experience and knowledge.

2 Set up AirSanifier temporarily.

We will set up a temporary **AirSanifier** immediately to start the process of protecting tenants and those working in the property. This will be left in place until remedial works are completed.

3 Check Ventilation.

We will check the efficiency of all extract fans in the property.

4 Conclude report.

We will provide a brief report on our finding including the ventilation efficiency.

5 Remove AirSanifier prior to treatment.

We will remove the **AirSanifier** prior to any treatment as any excess dust etc will potentially damage the **AirSanifier**. Trained operative may do this.

6 A.Spray any visible mould with FloodHit and wipe down. B.Apply BioTouch.

We will remove the **AirSanifier** prior to any treatment as any excess dust etc will potentially damage the **AirSanifier**. Trained operative may do this.

6a. We will spray any visible mould as well as surrounding walls / surfaces with **FloodHit™** this is a proven kill rate of 99.9999999%and returns back to hydrogen and oxygen within minutes.

6b. We will then apply **BioTouch™** which will continue to protect surfaces until remedial works are complete and beyond.

7 Carry out strip out works.

The approved contractor should carry out any strip out works and remediation. If only minor remedial works required bypass to step 11?

8 Following strip out works.

Apply **FloodHit™** to any areas showing mould or has been wet.

9 Apply BioTouch.

We will then apply **BioTouch™** which will continue to protect surfaces until remedial works are complete and beyond.

10 Commence drying.

If required commence drying programme and certify dry after remedial works.

11 Install an AirSanifier.

Re install the temporary **AirSanifier** previously set aside or install one permanently.